

15 -ാം കേരള നിയമസഭ

14 -ാം സമ്മേളനം

നക്ഷത്ര ചിഹ്നം ഇല്ലാത്ത ചോദ്യം നം. 1391

19-09-2025 - ൽ മറുപടിയ്ക്ക്

ദേശീയപാത 66 ഇടിഞ്ഞു താഴ്ന്ന സംഭവം

ചോദ്യം		ഉത്തരം	
ശ്രീ. യു. എ. ലത്തീഫ്, ശ്രീ. എൻ. എ. നെല്ലിക്കുന്ന്, ശ്രീ. കുറുക്കോളി മൊയ്തീൻ, ശ്രീ. മഞ്ഞളാംകുഴി അലി		ശ്രീ. പി.എ. മുഹമ്മദ് റിയാസ് (പൊതുമരാമത്ത് വിനോദസഞ്ചാര വകുപ്പ് മന്ത്രി)	
(എ)	മലപ്പുറം കൂരിയാട് ദേശീയ പാത 66-ൽ ആറുവരി പാതയും സർവ്വീസ് റോഡും വിള്ളൽ വീണ് തകർന്ന സംഭവം സംബന്ധിച്ച് അന്വേഷണം നടത്തിയിട്ടുണ്ടോ;	(എ)	മലപ്പുറം കൂരിയാട് ദേശീയ പാത 66-ൽ ആറുവരി പാതയും സർവ്വീസ് റോഡും വിള്ളൽ വീണ് തകർന്ന സംഭവം സംബന്ധിച്ച് അന്വേഷണം നടത്തിയിട്ടുണ്ട് എന്ന് നിർമ്മാണ ചുമതലയുള്ള ദേശീയപാത അതോറിറ്റി അറിയിച്ചിട്ടുണ്ട്. ദേശീയ പാതയിൽ കേടുപാടുകൾ സംഭവിച്ച ഭാഗങ്ങൾ, ഉണ്ടായ കേടുപാടുകൾ, സ്വീകരിച്ച നടപടികൾ, റോഡുകൾ പൂർവ്വസ്ഥിതിയിലാക്കാൻ ഉദ്ദേശിക്കുന്ന തീയതി എന്നീ വിശദവിവരങ്ങൾ ദേശീയപാത അതോറിറ്റി അറിയിച്ചത് അനുബന്ധമായി ചേർക്കുന്നു.
(ബി)	പ്രസ്തുത ദേശീയ പാതയിൽ മറ്റ് ഏതെല്ലാം പ്രദേശങ്ങളിലെ റോഡുകൾക്കും സർവ്വീസ് റോഡുകൾക്കും കേടുപാടുകൾ ഉണ്ടായിട്ടുണ്ട്;	(ബി)	എ പിരിവിന്റെ അതേ മറുപടി
(സി)	നിർമ്മാണത്തിലെ അപാകതകളും ക്രമക്കേടുകളും റോഡുകൾ തകരാൻ കാരണമായിട്ടുണ്ടോയെന്ന് പരിശോധിച്ചിട്ടുണ്ടോ;	(സി)	എ പിരിവിന്റെ അതേ മറുപടി
(ഡി)	തകർന്ന റോഡുകൾ എപ്പോൾ പൂർവ്വസ്ഥിതിയിലാക്കും; അതിനായി ഇതുവരെ സ്വീകരിച്ച നടപടികൾ വിശദമാക്കുമോ?	(ഡി)	എ പിരിവിന്റെ അതേ മറുപടി

സെക്ഷൻ ഓഫീസർ

National Highways Authority of India
Regional Office-Kerala
Annexure-A

S. No.	Name of the Project	Brief Details of Failure/ Collapse	Action Taken	Anticipated completion date
1	Chengala-Neeleshwaram Section of NH-66	Incident of soil nailing collapse in Ch. 58+035 to Ch. 58+100 (RHS) in Chengala-Neeleshwaram Section of NH-66. Moreover, cracks in MCW and SR has been observed at many locations along the project reaches. Under construction slab of VUP at Ch. 72+927 on LHS was collapsed during the concreting on 29.10.2022 due to failure of staging of material	M/s. Megha Engineering & Infrastructure Ltd. debarred upto 1 year or completion of rectification work, whichever is later + penalty of 5% of Current value of failed work or 0.5% of Contract value of whole work whichever is more. Since the project is under HAM (Hybrid Annuity Model) mode, any damages will be rectified by the Concessionaire at their own cost and slope protection will be carried out as per Expert committee suggestions. Rs. 0.30 Crs was imposed on the contractor	30.09.2025
2	Four laning of Thalassery Mahe Bypass	Due to Collapse of 4 No. of girders during construction	Rs. 1.0 Cr was imposed on the contractor	Project Completed
3	Six laning of Ramanattukara Junction to start of Valanchery bypass	An incident involving embankment settlement and failure of RE Wall occurred between Ch. 276+800 and Ch. 277+050 (LHS) of Ramanattukara - Valanchery Section of NH-66 in Kerala on 19th May 2025 when the project is nearing completion. The highway consists of six lane main carriage way and service roads on either side.	Debarment notice issued to M/s. KNR construction Ltd. for debarment upto 1 year + penalty of 5% of Current value of failed work or 0.5% of Contract value of whole work whichever is more. Concessionaire & IE has approached Delhi High Court against such action. A viaduct is being constructed at the risk and cost of the concessionaire	31.12.2025
4	Thuravoor-paravoor	Collapse of P17-18 span of 4 PSC girders. The work was carried out as per approved design, drawing and methodology. After the erection of the girders in position bracings within the girder had been completed. Bearings were in position. Cross girders were yet to be casted. The support to girders were with wooden blocks on sand jacks. On site enquiry it was intimated by the representative of the contractor at site that the workers mistakenly removed the support for using it for subsequent girders. The workers removed the sand jack & wooden blocks of Girder no-G4 first & then Girder no-G3, Girder no-G2 and G1 of Pier No-18. The process was continued for Pier No-17 in the same sequence. It was about to remove the packing of G1 then the Girder no-G4 started moving away. The girder no-G4 moved away from its position and along with all other girders of the span P17-P18 simultaneously fell to ground. The workers, seeing the girder moving from its position quickly moved away from its position.	Girders relaunched	31.07.2025
5	Kollam Bypass to Kadambattukonam	Failure/Collapse of Scaffolding of Minor Bridge (under construction) at Km. Ch. 497+370 (RHS)	Penalty of Rs. 9.55 lakhs was imposed on concessionaire and concessionaire has terminated the service of the Engineer responsible.	31.03.2026