ടെലിഫോൺ നമ്പർ : 2512524 പോസ്റ്റ് ബോക്സ് നമ്പർ : 5430 ഫാക്സ് : 0471-2305891 പിൻ കോഡ്-695 033







ഇ-മെയിൽ: secretary@niyamasabha.nic.in

കേരള നിയമസഭാ സെക്രട്ടേറിയറ്റ്

നം.12676/കെ.എൽ.(എ.സി.)എ 1/2023/നിസെ.

തിരുവനന്തപുരം, 25.09.2023.

ദർഘാസ് പരസ്യം

2023 നവംബർ 1 മുതൽ 7 വരെ നിയമസഭ സമുച്ചയത്തിൽ നടത്താൻ ഉദ്ദേശിക്കുന്ന കേരള നിയമസഭ അന്താരാഷ്ട്ര പുസ്തകോത്സവം രണ്ടാം പതിപ്പുമായി ബന്ധപ്പെട്ട് ഇതോടൊപ്പം ഉള്ളടക്കം ചെയ്തിരിക്കുന്ന സ്പെസിഫിക്കേഷൻ പ്രകാരം നിയമസഭാ സമുച്ചയത്തിലും പരിസരത്തും വൈദ്യുത ദീപാലങ്കാരം ഏർപ്പെടുത്തുന്നതിനും മറ്റ് അനുബന്ധ ക്രമീകരണങ്ങൾ സജ്ജീകരിക്കുന്നതുമായി ബന്ധപ്പെട്ട പ്രവൃത്തികൾ ചെയ്യുന്നതിന് സന്നദ്ധതയുള്ളവരിൽ നിന്ന് മുദ്രവച്ച കവറിൽ ദർഘാസുകൾ ക്ഷണിച്ചുകൊള്ളുന്നു.

വിശദാംശം

ദർഘാസ് ഫാറത്തിന്റെ വില - ₹2400+12% ജി.എസ്.ടി.

നിരത്യവ്യം - ₹12000/-

ദർഘാസ് ഫാറങ്ങൾ വിതരണം ചെയ്യന്ന

അവസാന തീയതി - 30.09.2023 രാവിലെ 10.30 മണി

ദർഘാസുകൾ സ്വീകരിക്കുന്ന അവസാന തീയതി - 03.10.2023 ഉച്ചയ്ക്ക് ശേഷം 2.00 മണി

ദർഘാസുകൾ തുറക്കുന്ന തീയതി - 04.10.2023 ഉച്ചയ്ക്ക് ശേഷം 03.00 മണി

നിബന്ധനകൾ ഉൾക്കൊള്ളുന്ന ദർഘാസ് ഫാറം സ്റ്റേജ്, ഡെക്കറേഷൻ & സ്റ്റാൾ കമ്മിറ്റി കൺവീനർ, നിയമസഭാ സെക്രട്ടേറിയറ്റിൽ നിന്ന് (റ്റം നമ്പർ 805, നാലാം നില, അസംബ്ലി ബിൽഡിംഗ്) ലഭിക്കുന്നതാണ്. ദർഘാസ് സമർപ്പിക്കുന്ന കവറിന് പുറത്ത് " 'KLIBF -2nd Edition'- നിയമസഭാ സമുച്ചയത്തിൽ വൈദ്യുത ദീപാലങ്കാരം, മറ്റ് അനബന്ധ ക്രമീകരണങ്ങൾ എന്നിവ ഏർപ്പെടുത്തുന്നതിനുള്ള ദർഘാസ്" എന്ന് രേഖപ്പെടുത്തേണ്ടതാണ്. ദർഘാസ് ഫാറത്തിന്റെ വില

മടക്കി നൽകുന്നതല്ല. ദർഘാസ് ഫാറങ്ങൾ കൈമാറ്റം ചെയ്യാൻ പാടുള്ളതല്ല. 03.10.2023-ന് അവധി ആണെങ്കിൽ തൊട്ടടുത്ത ദിവസം രാവിലെ 11.00 പ്രവത്തി മണിവരെ ദർഘാസുകൾ സ്വീകരിക്കുന്നതം അന്നേദിവസം 3.00 ഉച്ചയ്ക്കശേഷം മണിയ്ക്ക് പരിശോധിക്കുന്നതുമാണ്. നിശ്ചിത സമയപരിധിക്കുള്ളിൽ ലഭിക്കാത്ത ദർഘാസുകൾ സ്വീകരിക്കുന്നതല്ല. പ്രവ്വത്തി ചെയ്യന്നതിനാവശ്യമായ പരമാവധി സമയം ദർഘാസിൽ സൂചിപ്പിക്കേണ്ടതാണ്. ക്വാട്ട് ചെയ്യുന്ന നിരക്ക് എല്ലാ നികതികളം ചെലവുകളം ഉൾപ്പെടെ ആയിരിക്കണം. നിയമസഭയിൽ നിന്ന് വിതരണം ചെയ്യന്ന ദർഘാസ് ഫാറത്തോടൊപ്പം കേരള സംസ്ഥാനത്ത് നിന്ന് വാങ്ങിയ 200/-രൂപയുടെ മുദ്രപത്രത്തിൽ എഗ്രിമെന്റം മറ്റ് ബന്ധപ്പെട്ട സമർപ്പിക്കേണ്ടതാണ്. പ്രസ്തത പ്രവ്വത്തി ചെയ്യന്നതിന് സന്നദ്ധതയുള്ളവർക്ക് 30.09.2023 രാവിലെ 11.00 മണിക്ക് ചേരുന്ന പ്രീ-ബിഡ് മീറ്റിംഗിൽ പങ്കെടുത്ത് സംശയനിവാരണം നടത്താവുന്നതാണ്.

ദർഘാസുകൾ സ്വീകരിക്കുന്നതിനോ യാതൊരു കാരണവും വൃക്തമാക്കാതെ നിരസിക്കുന്നതിനോ നിയമസഭാ സെക്രട്ടറിക്ക് അധികാരമുണ്ടായിരിക്കുന്നതാണ്.

> ഷബാന അഞ്ജം, ജോയിന്റ് സെക്രട്ടറി & കൺവീനർ,

സ്റ്റേജ് ഡെക്കറേഷൻ & സ്റ്റാൾ കമ്മിറ്റി KLIBF – Edition II ഫോൺ നമ്പർ 0471 - 2512498

നിബന്ധനകൾ

- സമാനമായ പ്രവൃത്തികൾ നടത്തി പരിചയമുണ്ടായിരിക്കണം; PWD Electrical Wing Registered Contractor ആയിരിക്കണം; പരിചയ സർട്ടിഫിക്കറ്റ് ഹാജരാക്കണം.
- 2. അളവുകളിൽ 25% വരെ വ്യതിയാനം വരുത്താവുന്നതാണ്.
- ആവശ്യം വരുന്നപക്ഷം അധികമായി ക്രമീകരണങ്ങൾ നിർദ്ദേശാനസരണം ലഭ്യമാക്കേണ്ടതാണ്.
- 4. ടെണ്ടർ ഡോക്യുമെന്റ്സ് വാങ്ങുന്ന കോൺടാക്ടർമാർ ആവശ്യമുള്ള പക്ഷം പ്രീ-ബിഡ് മീറ്റിംഗിൽ പങ്കെടുക്കാവുന്നതാണ്.
- 5. നിശ്ചിത ദിവസത്തിനകം പ്രവ്വത്തി പൂർത്തീകരിക്കണം.
- പ്രസ്തത പ്രവൃത്തി പൊതുമരാമത്ത് ഉദ്യോഗസ്ഥങ്ങടെ നിർദ്ദേശപ്രകാരവും നിബന്ധന പ്രകാരവും നടത്തേണ്ടതാണ്.
- 7. പ്രസ്തത പ്രവ്വത്തികൾ നിർവ്വഹിക്കുന്നതിനായി ആവശ്യാനുസരണം ജോലിക്കാരെ (skilled and unskilled) സൈറ്റിൽ ലഭ്യമാക്കേണ്ടതാണ്. ക്രമീകരണങ്ങളിൽ/ പ്രവ്വത്തികളിൽ പിഴവുകൾ വരുന്ന പക്ഷം ആയത് സമയബന്ധിതമായി മാറ്റി സ്ഥാപിക്കുകയോ പരിഹരിക്കുകയോ ചെയ്യേണ്ടതാണ്.
- 8. സെറ്റിൽ ആവശ്യത്തിന് stand by സാധനങ്ങൾ ലഭ്യമാക്കേണ്ടതാണ്.
- 9. ഏതെങ്കിലും കാരണവശാൽ പ്രവൃത്തികളിൽ വീഴ്ച വരുത്തിയാൽ നിയമാനുസൃതമായ പിഴ ഈടാക്കുന്നതാണ്.

ദർഘാസ് അധികാരിയുടെ ഒപ്പ്

കരാറുകാരന്റെ ഒപ്പ്

Name	of Work		KLIBF 2023 Second Edition - Providing Temporary Illumination and Security	Lights in Legislatu	re Compound
			and the second of the second o	Janes Leading Control	
	1 -		CFYOM	01:11-2023 to 0	म -।।-१०१३)
SI No.		Unit	Specification	Rate Without GST	Amount
1	20	each set	Hire and labour charges for providing 1x20W LED tube fittings with tube as directed in position and giving connection for1st day		
2	20	each set	Hire and labour charges for providing 1x20W LED tube fittings with tube as directed in position and giving connection for 2nd day		
3	100	each set	Hire and labour charges for providing 1x20W LED tube fittings with tube as directed in position and giving connection for 3rd day to final day		
4	20	each set	Hire & Damp; labour charges for providing 65W LED lamp with holder and wiring using 2.5 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire for 1st day		
5	20	each set	Hire & LED lamp with holder and wiring using 2.5 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire for 2nd day		
6	100	each set	Hire & LED lamp with holder and wiring using 2.5 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire for 3rd day to final day		
7	3500	each set	Hire and labour charges for providing LED pixel serial set consisting of 50 nos LED lamps along with driver as directed in position and giving connections etc. as required for 1st day		
8	3500	each set	Hire and labour charges for providing LED pixel serial set consisting of 50 nos LED lamps along with driver as directed in position and giving connections etc. as required for 2nd day	- ····································	
) 	17500	each set	Hire and labour charges for providing LED pixel serial set consisting of 50 nos LED lamps along with driver as directed in position and giving connections etc. as required for 3rd day to final day		

Sl No.	Qty	Unit	Specification	Rate Without GST	Amount
10	100	each set	Hire and labour charges for providing 100W / 150 W LED flood light (Warm, White or Green Colour) and wiring using 4 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 1st day		
11	100	each set	Hire and labour charges for providing 100W / 150 W LED flood light (Warm, White or Green Colour) and wiring using 4 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 2nd day		
12	500	each set	Hire and labour charges for providing 100W / 150 W LED flood light (Warm, White or Green Colour) and wiring using 4 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 3rd day final day		
13	60	each set	Hire and labour charges for providing LED PAR light fitting and wiring using 4 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 1st day		
14	60	each set	Hire and labour charges for providing LED PAR light fitting and wiring using 4 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 2nd day		
15	300	each set	Hire and labour charges for providing LED PAR light fitting and wiring using 4 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 3rd day to final day		
16	4	each set	Hire and labour charges for providing LED Spot Moving Head Sharpy Light with necessary connecting wires for 1st day		
17	4	each set	Hire and labour charges for providing LED Spot Moving Head Sharpy Light with necessary connecting wires for 2nd day		

Sl No.	Qty	Unit	Specification	Rate Without GST	Amount
18	20		Hire and labour charges for providing LED Spot Moving Head Sharpy Light with necessary connecting wires for 3rd day to final day		
19	5	each set	Hire and labour charges for providing LED spot light warm colour and wiring using 1.5 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 1st day		· · · · · · · · · · · · · · · · · · ·
20	5	each set	Hire and labour charges for providing LED spot light warm colour and wiring using 1.5 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 2nd day		 -
21	25	each set	Hire and labour charges for providing LED spot light warm colour and wiring using 1.5 sqmm FRLS PVC insulated copper wire clipped in No12 GI wire in position and giving connections etc. as required for 3nd day to final		···
22	4	each set	Hire and labour charges for providing LED Fresnel spot light for 1st day		<u></u>
23	4	each set	Hire and labour charges for providing LED Fresnel spot light for 2nd day		
24	20		Hire and labour charges for providing LED Fresnel spot light for 3rd day to final day		
25	25	each set	Hire and labour charges for providing 2 to 3W LED candle lamp with holder and wiring using 1.5sqmm FRLS PVC insulated copper wire to be hung as directed in position and giving connections etc. as required for 1st day		
26	25	each set	Hire and labour charges for providing 2 to 3W LED candle lamp with holder and wiring using 1.5sqmm FRLS PVC insulated copper wire to be hung as directed in position and giving connections etc. as required for 2nd day		
27	125	each set	Hire and labour charges for providing 2 to 3W LED candle lamp with holder and wiring using 1.5sqmm FRLS PVC insulated copper wire to be hung as directed in position and giving connections etc. as required for 2nd day		
28	100	each set	Hire and labour charges for providing light duty pedestal fan and giving connection for 1st day		

Sl No	. Qty	Unit	Specification	Rate Without GST	Amount
29	100	each set	Hire and labour charges for providing light duty pedestal fan and giving connection for 2nd day		***************************************
30	500	each set	Hire and labour charges for providing light duty pedestal fan and giving connection for 3rd day to final day		
31	150	each set	Hire and labour charges for providing 6A 1 way switch & modular socket in suitable box and		
 			wiring using 1.5 sqmm FRLS PVC insulated single core copper cable with 2.5 sqmm FRLS wire as earth wire for 1st day		
32	150	each set	Hire and labour charges for providing 6A 1 way switch & amp;6A modular socket in suitable box and		· <u></u> <u></u>
:			wiring using 1.5 sqmm FRLS PVC insulated single core copper cable with 2.5 sqmm FRLS wire as earth wire for 2nd day		
33	750	each set	Hire and labour charges for providing 6A 1 way switch & amp;6A modular socket in suitable box and	-	·· ···································
			wiring using 1.5 sqmm FRLS PVC insulated single core copper cable with 2.5 sqmm FRLS wire as earth wire for 3rd day to final day		·
34	25	each set	Hire and labour charges for providing 16A 1 way switch & Damp; 16A modular socket in suitable box and		
			wiring using 2.5 sqmm FRLS PVC insulated single core copper cable with 2.5 sqmm FRLS wire as earth wire for 1st day		
35	25	each set	Hire and labour charges for providing 16A 1 way switch & to A modular socket in suitable box and		- · - · - · · · · · · · · · · · · · · ·
			wiring using 2.5 sqmm FRLS PVC insulated single core copper cable with 2.5 sqmm FRLS wire as earth wire for 2nd day		

Sl No.	Qty	Unit	Specification	Rate Without GST	Amount
36	125	each set	Hire and labour charges for providing 16A 1 way switch & modular socket in suitable box and wiring using 2.5 sqmm FRLS PVC insulated single core copper cable with 2.5 sqmm FRLS wire as earth wire for 3rd day to final day		
37	10	each set	Hire and labour chrges for providing room coolers (20 to 25 litter) With Everlast Pump, 4-Way Air Deflection And High Density Honeycomb Pads, unit in position and giving connections for 1st Day		
38	10	each set	Hire and labour chrges for providing room coolers (20 to 25 litter) With Everlast Pump, 4-Way Air Deflection And High Density Honeycomb Pads, unit in position and giving connections for 2nd Day		
39	50	each set	Hire and labour charges for providing room coolers (20 to 25 litter) With Everlast Pump, 4-Way Air Deflection And High Density Honeycomb Pads, unit in position and giving connections for 3rd day to final Day		
40	5	each	Hire and labour charges for providing 62KVA Generator with operator as directed in position and giving connections etc. as required for 1st day		F .NV
41	5	each	Hire and labour charges for providing 62KVA Generator with operator as directed in position and giving connections etc. as required for 2nd day		·····
42	25	each	Hire and labour charges for providing 62KVA Generator with operator as directed in position and giving connections etc. as required for3rd day to final day		
43	280	each set	Running charges for 62KVA Generator set including supply of fuel		
44	4	each set	Hire and labour charges for providing 100A, 4 pole On-Load Change Over Switches In SS Enclosure and giving connection for 1st day		
45	4	each set	Hire and labour charges for providing 100A, 4 pole On-Load Change Over Switches In SS Enclosure and giving connection for 2nd day		
46	20	each set	Hire and labour charges for providing 100A, 4 pole On-Load Change Over Switches In SS Enclosure and giving connection for 3rd day to final day		

Sl No.	Qty	Unit	Specification	Rate Without GST	Amount
47	500	metre	Hire and labour charges for providing 3.5x50 sqmm PVC insulated and PVC sheathed armored Al cable of 1.1 KV grade for 1st day		
48	500	metre	Hire and labour charges for providing 3.5x50 sqmm PVC insulated and PVC sheathed armoured Al cable of 1.1 KV grade for 2nd day		·
49	2500	metre	Hire and labour charges for providing 3.5x50 sqmm PVC insulated and PVC sheathed armored Al cable of 1.1 KV grade for 3rd day to final day		
50	3	each set	Hire and labour charges for providing 3 phase 6W TPN VDB with 100A 4P Isolator, and SP/TPMCBs as directed in position and giving connections etc. as required for		
51	3	each set	Hire and labour charges for providing 3 phase 6W TPN VDB with 100A 4P Isolator, and SP/TPMCBs as directed in position and giving connections etc. as required for 2nd day		
52	15	each set	Hire and labour charges for providing 3 phase 6W TPN VDB with 100A 4P Isolator, and SP/TPMCBs as directed in position and giving connections etc. as required for 3rd day to final day		
53	2	each set	Hire and labour charges for providing 3 phase 8W TPN VDB with 100A 4P Isolator, and SP/TPMCBs as directed in position and giving connections etc. as required for 1st day		
54	2	each set	Hire and labour charges for providing 3 phase 8W TPN VDB with 100A 4P Isolator, and SP/TPMCBs as directed in position and giving connections etc. as required for 2nd day		
55	10	each set	Hire and labour charges for providing 3 phase 8W TPN VDB with 100A 4P Isolator, and SP/TPMCBs as directed in position and giving connections etc. as required for 3rd day to final day		
56	1000	metre	Hire and labour charges for providing 4x16 sqmm PVC insulated and PVC sheathed armoured Al cable of 1.1 KV grade for first day		

.

Sl No.	Qty	Unit	Specification	Rate Without GST	Amount
57	1000	metre	Hire and labour charges for providing 4x16 sqmm PVC insulated and PVC sheathed armoured Al cable of 1.1 KV grade for additional one day		
58	5000	metre	Hire and labour charges for providing 4x16 sqmm PVC insulated and PVC sheathed armoured Al cable of 1.1 KV grade for additional one day		100
59	1000	metre	Hire and labour charges for providing 4x10 sqmm PVC insulated and PVC sheathed armoured Al cable of 1.1 KV grade for 1st day		
60	1000	metre	Hire and labour charges for providing 4x10 sqmm PVC insulated and PVC sheathed armoured Al cable of 1.1 KV grade for 2nd day		
61	5000	metre	Hire and labour charges for providing 4x10 sqmm PVC insulated and PVC sheathed armoured Al cable of 1.1 KV grade for 3rd day to final day		
62	9	each set	Hire and labour charges for providing 3 phase 8W MCBDB with 63A 4P Isolator,63A 4P RCCB and SPMCBs as directed in position and giving connections etc. as required for 1st day		
63	9	each set			
54	45	each set	Hire and labour charges for providing 3 phase 8W MCBDB with 63A 4P Isolator,63A 4P RCCB and SPMCBs as directed in position and giving connections etc. as required for 3rd day to final day		
55	10	each set	Hire and labour charges for providing 3 phase 4W MCBDB with 40A 4P Isolator, 40A 4P RCCB and SPMCBs as directed in position and giving connections etc. as required for 1st day		
56	10	each set	Hire and labour charges for providing 3 phase 4W MCBDB with 40A 4P Isolator, 40A 4P RCCB and SPMCBs as directed in position and giving connections etc. as required for 2nd day		

•

Sl No.	Qty	Unit	Specification	Rate Without GST	Amount
67	50	each set	Isolator, 40A 4P RCCB and SPMCBs as directed in position and giving connections etc. as required for 3rd day to final day	. 331	
68	1000	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 2.50 sq.mm 2 Run for 1st day		
69	1000	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 2.50 sq.mm 2 Run for 2nd day		
70	5000	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 2.50 sq.mm 2 Run for 3rd day to final day		
71	1000	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 2.50 sq.mm 4 Run for 1st day	<u> </u>	
72	1000	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 2.50 sq.mm 4 Run for 2nd day	· · · · · · · · · · · · · · · · · · ·	
73	5000	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 2.50 sq.mm 4 Run for 3rd day to final day		

Sl No.	Qty	Unit	Specification	Rate Without GST	Amount
	500	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 4 sq.mm 2 Run for 1st day		
7 5	500	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 4 sq.mm 2 Run for 2nd day		
76	2500	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 4 sq.mm 2 Run for 3rd day to final day		***************************************
77	300	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 4 sq.mm 4 Run for 1st day		
78	300	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 4 sq.mm 4 Run for 2nd day		
79	1500	metre	Hire and labour charges for drawing 650/1100 V grade FRLS PVC insulated stranded single core copper conductor cables conforming to IS 694 clipped with No 12 SWG GI wire and giving necessary connections of the following sizes. 4 sq.mm 4 Run for 3rd day to final day		
80	20	each set	Hire and labour charges for providing ordinary pipe earthing using 40mm dia GI pipe of including all accessories etc. as required for 1st day		

Sl No.	Qty	Unit	Specification	Rate Without GST	Amount	
81	20	each set	Hire and labour charges for providing ordinary pipe earthing using 40mm dia GI pipe of including all accessories etc. as required for 2nd day			
82	100	each set	Hire and labour charges for providing ordinary pipe earthing using 40mm dia GI pipe including all accessories etc. as required for 3rd day to final			
83	300	metre	Hire and labour charges for providing No 4 SWG bare copper conductor and giving connection for 1st day			
84	300	metre	Hire and labour charges for providing No 4 SWG bare copper conductor and giving connection for 2nd day		- 1	
85	1500	metre	Hire and labour charges for providing No 4 SWG bare copper conductor and giving connection for 3rd day to final day		··· ··· ··· ··· ··· ··· ··· ··· ··· ··	
86	300	metre	Hire and labour charges for providing No 10 SWG bare copper conductor and giving connection for 1st day			
87	300	metre	Hire and labour charges for providing No 10 SWG bare copper conductor and giving connection for 2nd day			
88	1500	metre	Hire and labour charges for providing No 10 SWG bare copper conductor and giving connection for 3rd day to final day			
89	50	metre	Hire and Labour charges for providing ABC fire extinguisher 5/6 Kg as directed in position for 1st day		·	
90	50	metre	Hire and Labour charges for providing ABC fire extinguisher 5/6 Kg as directed in position for 2nd day		· · · ·	
91	250	metre	Hire and Labour charges for providing ABC fire extinguisher 5/6 Kg as directed in position for 3rd day to final day		··	
			Total Quoted Amount(without GST)			
			GS	T Amount (18%)		
	·			Rounded off		
			Total Quoted A	mount(with GST)		